

WAC 296-54-571 Releasing spiked guylines and spiked skylines from anchors. The following procedures must be followed when removing spiked guylines or spiked skylines from stumps:

(1) Reversed safety wrap is put on and secured before loosening the last wrap;

(2) An authorized employee is in charge of loosening guylines or skylines;

(3) The authorized employee uses all precautions and gives warning before releasing lines; and

(4) Safety holdbacks are used when necessary for employee safety.

[Statutory Authority: RCW 49.17.010, [49.17].040 and [49.17].050. WSR 99-17-117, § 296-54-571, filed 8/18/99, effective 12/1/99. Statutory Authority: RCW 49.17.040, 49.17.150 and 49.17.240. WSR 79-10-081 (Order 79-14), § 296-54-571, filed 9/21/79.]