

WAC 51-11C-40804 Section C408.4—Service water heating systems commissioning.

C408.4 Service water heating systems commissioning. Service water heating equipment and controls subject to Section C404 shall be included in the commissioning process required by Section C408.1. The commissioning process shall minimally include all energy code requirements for which the code states that equipment or controls shall "be capable of" or "configured to" perform specific functions.

EXCEPTION: Service water heating systems are exempt from the commissioning process in buildings where the largest service water heating system capacity is less than 200,000 Btu/h (58.6 W) and where there are no pools or permanent spas.

C408.4.1 Functional performance testing. Functional performance testing specified in Sections C408.4.1.1 through C408.4.1.3 shall be conducted. Written procedures which clearly describe the individual systematic test procedures, the expected systems' response or acceptance criteria for each procedure, the actual response or findings, and any pertinent discussion shall be followed. Testing shall affirm operation with the system under 50 percent water heating load.

C408.4.1.1 Equipment. Equipment functional performance testing shall demonstrate the installation and operation of components, systems, and system-to-system interfacing relationships in accordance with approved plans and specifications such that operation, function, and maintenance serviceability for each of the commissioned systems is confirmed. Testing shall include all modes and *sequence of operation*, including under full-load, part-load and the following emergency conditions:

1. Redundant or *automatic* back-up mode;
2. Performance of alarms; and
3. Mode of operation upon a loss of power and restoration of power.

C408.4.1.2 Controls. Service water heating controls shall be tested to document that control devices, components, equipment, and systems are calibrated, adjusted and operate in accordance with approved plans and specifications. Sequences of operation shall be functionally tested to document they operate in accordance with *approved* plans and specifications.

C408.4.1.3 Pools and spas. Service water heating equipment, time switches, and heat recovery equipment which serve pools and permanent spas shall undergo a functional test to determine that they operate in accordance with manufacturer's specifications.

[Statutory Authority: RCW 19.27A.025, 19.27A.045, 19.27A.160, and 19.27.074. WSR 16-13-089, § 51-11C-40804, filed 6/15/16, effective 7/16/16. Statutory Authority: RCW 19.27A.025, 19.27A.160, and 19.27.074. WSR 16-03-072, § 51-11C-40804, filed 1/19/16, effective 7/1/16. Statutory Authority: RCW 19.27A.020, 19.27A.025 and chapters 19.27 and 34.05 RCW. WSR 13-04-056, § 51-11C-40804, filed 2/1/13, effective 7/1/13.]